BILL NO. S-85-07-10

SPECIAL ORDINANCE NO. S-140-85

AN ORDINANCE approving Change Order No. 1, Res. #404-84, Winchester Road Sanitary Sewer, with All Star Construction & Excavating, in connection with the Board of Public Works and Safety.

NOW, THEREFORE, BE IT ORDAINED BY THE COMMON COUNCIL OF THE CITY OF FORT WAYNE, INDIANA:

SECTION 1. That Change Order No. 1, Res. #404-84, Winchester Road Sanitary Sewer, with All Star Construction & Excavating, in connection with the Board of Public Works and Safety, for:

Change order #1 for Res. #404-84, Winchester Road Sanitary Sewer is necessary because of the following:

Bid Item #7 - 6" Building Sewer Extension - Due to alluvial and acquifer soil conditions, selected building sewers were extended beyond the proposed planned limits in order to protect existing utilities in particular, an existing 12" water main.

Bid Items #8 (#53/73 Special Backfill - #9 Special Back Fill - #10 Base Stabilization), due to alluvial soil and pockets of water bearing gravel, it became evident during construction that the existing road (Riverway Drive) was in danger of falling within the trench area. Due to the location of work to be performed and amount of said ground water, the WPC Engineering Department ordered the contractor to "overcut" the trench and sump pump out the water in lieu of very expensive well points. This required additional gravel and #53 stone for backfilling and restoration. Due to the above noted ground water, "base stabilization" for the pipe was required;

involving a net increase of Eight Thousand Three Hundred Forty-Eight and 89/100 Dollars ($8,348.89), all as more particularly set forth in the specifications, and which is on file with the Office of the Board of Public Works and Safety, and is by re-

ference incorporated herein, made a part hereof and is hereby in all things ratified, confirmed and approved.

SECTION 2. That this Ordinance shall be in full force and effect from and after its passage and any and all necessary approval by the Mayor.

Councilmember

APPROVED AS TO FORM
AND LEGALITY

Bruce O. Boxberger, City Attorney

FOX RIVER BOND
25% COTTON

Read the first time in full and on motion by Eisbart, seconded by Talarico, and duly adopted, read the second time by title and referred to the Committee City Utilities (and the City Plan Commission for recommendation) and Public Hearing to be held after due legal notice, at the Council Chambers, City-County Building, Fort Wayne Indiana, on _____, the _____ day of _____, 19____, at _____ o'clock ____.M.,E.S

DATE: 7-9-85

Sandra E. Kennedy
SANDRA E. KENNEDY, CITY CLERK

Read the ~~third~~ time in full and on motion by Henry, seconded by Talarico, and duly adopted, placed on its passage. PASSED ~~(LOST)~~ by the following vote:

	AYES	NAYS	ABSTAINED	ABSENT	TO-WIT:
TOTAL VOTES	8			1	
BRADBURY	✓				
BURNS	✓				
EISBART	✓				
GiaQUINTA	✓				
HENRY	✓				
REDD	✓				
SCHMIDT	✓				
STIER				✓	
TALARICO	✓				

DATE: 7-23-85

Sandra E. Kennedy
SANDRA E. KENNEDY, CITY CLERK

Passed and adopted by the Common Council of the City of Fort Wayne, Indiana, as ~~(ANNEXATION)~~ ~~(APPROPRIATION)~~ (GENERAL) (SPECIAL) ~~(ZONING MAP)~~ ORDINANCE ~~(RESOLUTION)~~ NO. G-140-85 on the 23rd day of July, 19 85,

ATTEST:

Sandra E. Kennedy
SANDRA E. KENNEDY, CITY CLERK

(SEAL)

Mark E. GiaQuinta
PRESIDING OFFICER

Presented by me to the Mayor of the City of Fort Wayne, Indiana, on the 24th day of July, 19 85, at the hour of 11:30 o'clock A.M.,E.S.T.

Sandra E. Kennedy
SANDRA E. KENNEDY, CITY CLERK

Approved and signed by me this 24th day of July, 19 85, at the hour of 4:00 o'clock P.M.,E.S.T.

WIN MOSES, JR., MAYOR

CHANGE ORDER

Change Order No. 1
Project No.
Name of Project: "Winchester Road Sanitary Sewer"

Resolution No. 404-1984
Board Order No. 89-1984
Date:

To: ALL STAR CONSTRUCTION & EXCAVATING
(Contractor)

Gentlemen:

You are hereby requested to comply with the following changes from the contract plans and specifications:

Item No.	Quantity	Description of Change: Description	Unit Price	Change in Contract Price: Decrease	Increase
7	25 LF	6" Building Sewer Extension	23.90		597.50
8	83 CY	#53/#73 Special Backfill	9.14		758.62
9	369 CY	Special Backfill	7.33		2,704.77
19	536 Tons	Base Stabilization	8.00		4,288.00
			Total Decrease		
			Total Increase		8,348.89
		Net (~~Decrease~~)(Increase)	Contract Price		8,348.89

The sum of $ 8,348.89 is hereby (added to) ~~(deducted from)~~ the total contract price and the final contract price shall be adjusted as follows:

Original Contract Price	$ 74,053.55
Current Contract Price Adjusted by Previous Change Order	$ 74,053.55
New Contract Price including this Change Order	$ 82,402.44

The time provided for completion in the contract for this project is (unchanged) ~~(increased)~~ (de~~creased~~) by -0- calendar days due to this Change Order. The date for completion of all work shall be N/A. Furthermore, this document shall become an amendment to the contract and all provisions of the contract shall apply hereto.

Recommended by: C. Duane Embury Chief Engineer Date June 8, 1985

Accepted by: Edward F. Fox Contractor Date 5/10/85

Approved by: C. Duane Embury City Engineer Date June 8, 1985

Approved by: David J. Kiert Owner Date 6/26/85

Cosette R. Simon

Laurena B. Comalvo

Attested by: Helen V. Gochenour Clerk Date 6/26/85

Change Order No. 1

Resolution No. 409-84

Board Order No. 89-84

REQUEST AND JUSTIFICATION FOR CHANGE

1. Necessity for change:

See Attached Justification

2. Will proposed change alter size of the project? Yes _____ No X

If yes, explain

3. Affect on operation and maintenance cost of this project:

N/A

Jamsheed Behrana, P.E. Project Engineer

Winchester Road Sanitary Sewer
Resolution 404-1984 - B.O. 89-1984
Justification for Change Order #1

Bid Item #7

Due to alluvial and acquifer soil conditions, selected building sewers were extended beyond the proposed planned limits in order to protect existing utilities, in particular, an existing 12" water main.

Bid Items #8, 9 and 10

Due to alluvial soil and pockets of water bearing gravel, it became evident during construction that the existing road (Riverway Drive) was in danger of falling within the trench area. Due to the location of work to be performed and amount of said ground water, the WPC Engineering Dpeartment ordered the contractor to "overcut" the trench and sump pump out the water in lieu of very expensive well points. This required additional gravel and #53 stone for backfilling and restoration. Due to the above noted ground water, "base stabilization" for the pipe was required.

7054 Admin. Appr.

TITLE OF ORDINANCE Change Order #1, Res. #404-84, Winchester Road Sanitary Sewer

DEPARTMENT REQUESTING ORDINANCE Board of Public Works & Safety S-85-07-10

SYNOPSIS OF ORDINANCE Change Order #1 for Res. #404-84, Winchester Road Sanitary Sewer is necessary because of the following:

Bid Item #7 - 6" Building Sewer Extension - Due to alluvial and acquifer soil conditions, selected building sewers were extended beyond the proposed planned limits in order to protect existing utilities in particular, an existing 12" water main.

Bid Items #8 (#53/73 Special Backfill - #9 Special Back Fill - #10 Base Stabilization, due to alluvial soil and pockets of water bearing gravel, it became evident during construction that the existing road (Riverway Drive) was in danger of falling within the trench area. Due to the location of work to be performed and amount of said ground water, the WPC Engineering Department ordered the contractor to "overcut" the trench and sump pump out the water in lieu of very expensive well points. This required additional gravel and #53 stone for backfilling and restoration. Due to the above noted ground water, "base stabilization" for the pipe was required.

EFFECT OF PASSAGE To facilitate completion of project.

EFFECT OF NON-PASSAGE

MONEY INVOLVED (DIRECT COSTS, EXPENDITURE, SAVINGS) Increase $8,348.89

ASSIGNED TO COMMITTEE

BILL NO. S-85-07-10

REPORT OF THE COMMITTEE ON CITY UTILITIES

WE, YOUR COMMITTEE ON CITY UTILITIES TO WHOM WAS REFERRED AN (ORDINANCE) (~~RESOLUTION~~) approving Change Order No. 1, Res. #404-84, Winchester Raod Sanitary Sewer, with All Star Construction & Excavating, in connection with the Board of Public Works and Safety

HAVE HAD SAID (ORDINANCE) (~~RESOLUTION~~) UNDER CONSIDERATION AND BEG LEAVE TO REPORT BACK TO THE COMMON COUNCIL THAT SAID (ORDINANCE) (~~RESOLUTION~~)

YES		NO
	THOMAS C. HENRY CHAIRMAN	
	JANET G. BRADBURY VICE CHAIRWOMAN	
	DONALD J. SCHMIDT	
	JAMES S. STIER	
	CHARLES B. REDD	

CONCURRED IN 7-23-85

SANDRA E. KENNEDY
CITY CLERK